



**SUMMARY OF BOQ of 6 lanes Bowling Civil Works (site visit available for more details)**

**جداول الكميات الأعمال المدنية**

**لتجهيز صالة البولينغ 6 خطوط (زيارة الموقع متاح لمزيد من التفاصيل لتقديم عرض شامل)**

**تجهيز مركز البولينغ عدد 6 خطوط Supply and installation of 6 Lane bowling center**

<b>CIVIL WORKS</b>	
No	ITEMS
1	Supply & Installation of Gypsum board Ceiling Bulk Head between machine room and bowling area
2	Curtain Wall Supply & Installation of Single layered Gypsum Wall panel between Public area and bowling area
3	Supply and Pour Floor Slab Screed Minimum 10cm Thickness
4	Seating Area 800x800x10mm Porcelain floor tiles
5	Seating Area Porcelain skirting
6	Supply & Installation of Gypsum board Ceiling
7	Bowling Reception desk, cabinets & Shoe racks
7. a	Paint on wall
7.b	Paint on ceiling
8	OVERHEAD TV Supports for display units
<b>MEP WORKS</b>	
1	Supply & Installation of all MEP work

- Proposal last submission date 07/01/2025 آخر موعد للتقديم 2025/01/07
- Vendors shall provide the services at the Employer site in Abu Dhabi - U.A.E. (Fatima Bint Mubarak على موقع المشروع ، ابوظبي، منطقة خور المقطع شارع 15 Ladies Sports Academy Building, Khor AL Maqta' Area – 15th Street 15
- Vendor must comply with all environmental health and safety majeures applied for relevant authorities in the Emirates of Abu Dhabi, UAE. على مقدم العرض التقيد بأحكام وشروط البيئة والصحة والسلامة والتصاريح اللازمة.



## **SUMMARY OF BOQ of 6 lanes Bowling Machines & Equipmnet (site visit available for more details)**

### **جداول الكميات للأجهزة والمعدات**

**لتجهيز صالة البولينغ 6 خطوط (زيارة الموقع متاح لمزيد من التفاصيل لتقديم عرض شامل)**

#### **1 PINSETTER - GS-NXT 400VAC (360 Controller)**

GS NXT Pinsetters With Standard Guarding Lane Pair (400v)	new	lane pair	3
GS NXT End Guards - For Standard Guarding	new	included	1
GS NXT White/ Blue LED Pin Light - For Centers With Sync Scoring	new	included	6
GS NXT Tool Kit (220v/380v)	new	included	1
Safety Labels - For UL Guarding	new	included	3
Three Phase "Wye" Power Arrestor (220/380v)	new	included	1

#### **2 CENTER MANAGEMENT & SCORING SYSTEM - SYNC**

Sync Small Center Server (220V)	new	lane pair	1
UPS For Sync Server (220V)	new	included	1
19" Flat Screen Touch Monitor	new	included	1
Sync Lane & Cash Control Software License	new	included	1
Front Desk Receipt Printer (220V)	new	included	1
Customer Pole Display (220V)	new	included	1

#### **SCORING SYSTEM - SYNC**

Sync Tablet <b>Console</b> - Coffe Table Mount	new	lane pair	3
Sync Display Controller - For Double Overheads	new	included	3
24-Port Network Switch For Sync Display Controller	new	included	1
24-Port Network Switch For Sync Tablet	new	included	1
220/380V Three Phase Power Arrestor	new	included	1

#### **OVERHEAD TV - COMMERCIAL GRADE**

50" Samsung LED Monitor (220v) - HDTV	new	lane	6
Continuous Support System	new	included	3
Mounting Brackets for Overhead Monitors	new	included	6

#### **3 LANE SYSTEM - ANVILANE & LANE ACCESSORIES**

Anvilane GID Two-Lane Pack	new	lane pair	3
Foundation Pair	new	included	3
Underlayment Pair	new	included	3
Pindeck For Synthetic Lanes	new	included	3
Flat Gutter	new	included	6

#### **Lane Accessories**

Ball Return Hood & Rack - Black	new	lane pair	3
Lower Profile Ball Rack - holds 10 balls	new	included	3
Power Ball Lift With Control Box (230v)	new	included	3
Ball Return Tracks	new	included	3

Return Capping - Matte Black Non-Glow	new	lane pair	3
Non-Glow Division Capping - Matte Black With Black Insert	new	included	6

Telefoul Two Lane Unit (230V)	new	lane pair	3
Return Telefoul Cover - Black Non-Glow	new	included	3
Telefoul Division Cover - Black Non-Glow	new	included	6

Matte Black Non-Glow Gutter with RAILS	new	lane pair	3
PBW 230Vac Automation	new	included	3

#### **4 MASKING WALL (by Customer Design)**

Led 1st & 2nd Ball Light	new	optional included	3
--------------------------	-----	-------------------	---



**5 FURNITURE (Center Stage CONFIG B 9ft.) consist of:**

<b>Coffee Table</b>	<b>new</b>	<b>each</b>	<b>3</b>
<u>Corner Units</u>	<i>new</i>	each	6
<u>Double Seat</u>	<i>new</i>	each	6
<u>Single Seat</u>	<i>new</i>	each	4
<u>Ottoman</u>	<i>new</i>	each	2

**6 CENTER SUPPLIES**

Houseballs - Urethane Drilled (asstd. Weight)	<b>new</b>	<b>each</b>	<b>60</b>
Premium Hook n Loop Rental Shoes - (asstd. Size)	<b>new</b>	<b>each</b>	<b>60</b>
Max Bowling Pins (3.6 - 3.9 oz.) GID (10pins/box)	<i>new</i>	box	15

**7 CENTER SPARE PARTS PACKAGE**

GS NXT Spare Kit	<i>new</i>	<i>set</i>	1
Sync Display Controller SPK	<i>new</i>	<i>each</i>	1
Spare Parts Kit For Sync Tablet Console	<i>new</i>	<i>each</i>	1
43" Samsung LED Monitor (220v) - HDTV	<i>new</i>	<i>each</i>	1

**8 CENTER LANE MAINTENANCE PACKAGE**

Phoenix LT4 - Lane Machine 230Vac	<i>new</i>	<i>Unit</i>	1
Lane Conditioner (2 x 2.5Gal)	<i>new</i>	<i>Box</i>	12
Lane Cleaner MAX (1x2.5Gal)	<i>new</i>	<i>each</i>	6

- Proposal last submission date 31/12/2024 2024/12/31 آخر موعد للتقديم
- Vendors shall provide the services at the Employer site in Abu Dhabi - U.A.E. (Fatima Bint Mubarak على موقع المشروع ، ابوظبي، منطقة خور المقطع شارع 15 Ladies Sports Academy Building, Khor AL Maqta' Area – 15th Street 15
- Vendor must comply with all environmental health and safety majeures applied for relevant authorities in the Emirates of Abu Dhabi, UAE. على مقدم العرض التقيد بأحكام وشروط البيئة والصحة والسلامة والتصاريج اللازمة.